

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

Register's Office }  
 Gogebic County } ss.

For corners in

Gogebic

(County)

Located In:

Corner Code #

- |                                    |                           |            |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey Sec. 8       | T <u>47N</u> R <u>46W</u> | <u>E-4</u> |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |

Received for record the  
21<sup>st</sup> day of JULY  
 A. D. 1995 at 1:35 o'clock  
P m., and recorded in  
 Liber 5 of CORNERS  
 on page 269

Ramona Collins DePitty  
 Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

1/4 cor. comm. to sec's. 8 & 9

I, John P. Goss, in a field survey on July 14, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt in June 1851. Set post.  
 Original bearing trees: Hemlock 8" S 82° W 16 links  
 Ironwood 6" N 86° E 33 links

John P. Goss in 1978 using MDOT plans found 1" sq. iron rod and recorded this corner in Liber 2 on page 386 of Land Corners for Gogebic County. He established the following witnesses and distance. 9" Maple- N 88° W- 13.58'; 3" Maple- S 26° W-7.31'; 2" Maple- N 10° E- 3.32'; 6" Maple- S 88° E- 33.49'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found the 1" sq. iron rod marking the corner position and it checked with the witnesses in John P. Goss certification. I Updated the corner monument and accessories as noted below to state and county specification.

Act 74 reseach on file with the County Register of Deeds Office.

**PEER GROUP APPROVED**

Richard P. Deahn 7/10/95  
 COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set a 2½" x 30" aluminum pipe with a 3¼" aluminum cap stamped as follows over the 1" sq. iron rod: County Remonumentation; T.47 N., R.46 W; 1/4; S-8, S-9; 1995; P.S. 23509. I established the following bearing trees and reference objects.

- |                        |         |        |
|------------------------|---------|--------|
| 13" Maple              | S 83° W | 34.58' |
| 10" Maple              | N 88° W | 13.58' |
| 7" Maple               | S 88° E | 33.62' |
| 4" Maple               | S 26° W | 7.31'  |
| 6' Steel rail and sign | N 50° E | 1.12'  |



Signed by John P. Goss  
 Surveyor's Michigan License No. P.S. 23509

Date July 14, 1995

Fed. No. G-9