

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
 Gogebic County } ss.

For corners in GOGEBIC
 (County)

Located In: _____ Corner Code # _____

| | | | | | |
|--------------------------------------|---|-----------|---|-----------|------------|
| 1. Public Land Survey | T | <u>47</u> | R | <u>46</u> | <u>F-7</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |
| 3. Miscellaneous Property in Section | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |

Received for record the
21st day of JULY
 A. D. 1995 at 1:40 o'clock
9 m., and recorded in
 Liber 5 of CORNERS

page 274
Harmona Collins, Deputy
 Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

$\frac{1}{4}$ Corner common to Section 16 & 21, T47N R46W

I, Earl W. Applekamp, in a field survey on May 24, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 6 | 5 | 4 | 3 | 2 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt, U.S. Deputy Surveyor, June 1851. Set Post.

Original Bearing Trees:

Cedar 12" S36°E 25 Links (16.50 feet)
 Y. Birch 14" N30°W 13 Links (8.58 feet)

PEER GROUP APPROVED
Richard L. Wzahn 7/18/95
 COUNTY Macomb IN T. 46 E.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

An Iron Pin was found at the intersection of Hill Avenue and Barber Street, Yale Location, City of Bessemer. This location is shown on the plat map as the South $\frac{1}{4}$ Corner of Section 16. The location is in agreement with the surrounding streets. I accepted the position and monumented the corner as described in (C.) below. Top of monument is 2" below top of blacktop.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a $\frac{3}{4}$ "x20" aluminum rod with a $\frac{3}{4}$ " cap stamped to read COUNTY REMONUMENTATION, $\frac{1}{4}$ S16, S21, T47N R46W, 1995, P.S. 17610. I established the following bearing trees and reference objects:

P. Pole N71°W 47.58 feet - 2 $\frac{1}{2}$ " Aluminum Pipe with $\frac{3}{4}$ " stamped cap. Witness Monument East 41.73 feet

P. Pole N60°E 33.10 feet - 18" Red Pine S42°W 62.43 feet



Signed by Earl W. Applekamp Date July 07, 1995
 Surveyor's Michigan License No. 17610