

1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
16th day of DECEMBER
A. D. 1993 at 2:30 o'clock
P m., and recorded in
Liber 4 of CORNERS
on page 314
Betty Lewis Deputy
Register of Deeds

Register of Deeds Stamp & File Number

For corners in

Gogebic
(County)

Located In:

Corner Code #

- 1. Public Land Survey Section 3 T 47N R 46W G-2
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____
One-quarter corner S-3 & S-4, T47N, R46W.

I, John R. Garske, in a field survey on December 2, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by Austin Burt, U.S.D.S., on June 14, 1851. Set post from which a 6" sugar bears S49°E, 32 links and a 8" sugar bears N82°W, 18 links. No evidence found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a R.R. spike marking the corner position at the center line - center line intersection of Stone Road and North Moore Road. This corner has been used and accepted in several surveys of record by several surveyors and has existed in harmony for many years.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Established the following bearing trees and reference objects:

- 16" sugar - N44°E - 47.05 feet
- N.W. cor. garage - S58°E - 115.05 feet

Reference monument - set a standard 2 1/2" x 30" aluminum pipe with a 3 1/4" aluminum cap stamped: County Remonumentation; T47N, R46W; 1/4 cor.; due east - 43.20 feet; R.M.; 1993; RLS 28410. Steel sign post - due west - 45.85 feet.

Reference monument - same as above - S31°W - 65.10 feet - Steel sign post - 1.50 feet

Signed by John R. Garske Date 12/27/93
Surveyor's Michigan License No. 28410

