

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
 Gogebic County } ss.

Received for record the
21st day of JULY
 A. D. 1995 at 1:40 o'clock
P m., and recorded in
 Liber 5 of CORNERS
 on page 270
Ramona Collins, Deputy
 Register of Deeds

Register of Deeds Stamp & File Number

For corners in

Gogebic
 (County)

Located in:

Corner Code #

- | | | | |
|------------------------------------|-------------------------|---------------------------|------------------------|
| 1. Public Land Survey | Sec. 9 | T <u>47N</u> R <u>46W</u> | <u>4</u>
<u>G-X</u> |
| | | T _____ R _____ | _____ |
| | | T _____ R _____ | _____ |
| | | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ | _____ |
| | S _____ T _____ R _____ | _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ | _____ |
| | S _____ T _____ R _____ | _____ | _____ |

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

1/4 cor. comm to sec's. 9 & 10

I, John P. Goss, in a field survey on July 16, 1995

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt in June 1851. Set post.
 Original bearing trees: Fir 10" S 75° W 21 links
 Fir 8" East 12 links

John P. Goss in 1977 using MDOT plan of U.S. #2 found railroad spike at location of corner. He recorded this corner in Liber 1 on page 335 of Land Corners for Gogebic County. He established the following witnesses and distances. P.Pole- S 46° W- 35.02'; P.Pole S 30° E- 40.68'; Center nut top Fire Hyd.- N 27° W- 48.27'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found a Railroad spike at the corner position and it checked with John P. Goss certification. I updated the corner monument accessories as noted below to state and county specification.

Act 74 reseach on file with the County Register of Deeds Office.

PEER GROUP APPROVED

Richard R. Dredger 7/19/95
 COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set a 2½" brass cap with a 2" stem over the railroad spike at 1" below asphalt road surface. Cap is stamped T.47 N., R.46 W.; 1/4; S-9, S-10; 1995, P.S. 23509. I established the following bearing trees and reference objects.

Center of Nut top of Fire Hyd. N 27° W 48.27'
 P.Pole S 27° E 40.75'
 16" N. Pine S 58° W 53.47'
 9" tw. Maples N 85° E 35.68'
 Reference Monument consisting of 2½" x 30"
 aluminum monument with a 3¼" aluminum cap
 stamped to indicate corner position.
 N 79° W- 24.40'



Signed by John P Goss

Date July 16, 1995

Surveyor's Michigan License No. P.S. 23509