

**SURVEY & REMONUMENTATION**

JAN 22 1998

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in \_\_\_\_\_  
Gogebic  
(County)

Located in: Section 22 47N 46W Corner Code # G-7

1. Public Land Survey	T	R	_____
	T	R	_____
	T	R	_____
	T	R	_____
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

Register's Office }  
Gogebic County } ss.

Received for record the  
2<sup>ND</sup> day of DECEMBER  
A. D. 1997 at 10:35 o'clock  
11 m., and recorded in  
Liber 6 of CORNERS  
on page 279  
Ramona Collins Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

1/4 corner section 15, 16, 21 & 22, T47N, R46W

I, John R. Garske, in a field survey on November 16, 1997 hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by Austin Burt, D.S. on June 12, 1851. He set a wood post from which:  
Yellow Birch 18" S51°W 27 links  
Hemlock N56°E 27 links  
Sugar 16" - 3.91 chains north  
- March 2, 1936 - USDA Survey form 87 - 4 indicates corner in road but not original.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I established the corner at the intersection on ancient north, south, east and west fence lines. Distances to existing monumented corners west and south check good with this location. Distances to old E-W fence lines north and south also check.

(Research on file)

**PEER GROUP APPROVED**  
Richard H. Deahn 12/1/97  
COUNTY REGISTER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I set a 2 1/2" x 30" alum pipe monument with a 3 1/4" dia. alum. cap stamped to identify the corner, from which:  
11" maple S32°W 22.58 feet  
6" Maple N45°W 28.82 feet  
4" Ash S87°E 18.32 feet  
Steel Sign Rail S70°W 1.78 feet

Signed by John R. Garske  
Surveyor's Michigan License No. 28410

Date \_\_\_\_\_

