OCT 9 3 1395

COMMISSION

_	COMMISSION		ER RECORDATION rement of Act 74, N		Kegis Gogel	fer's Off bic Cour	,				
	or corners in ogebic (County)	Located In:	Corner Code	#		16 74		Auc	057		
1.	Public Land Survey Section 28	T R	<u></u>		Liber	19.96 1 m	., and	710001	ded to		
2.		T R ST R ST R	·			none	Chlic		eput Deeds		
3.	Miscellaneous	ST R ST R	T R <u></u>			ister of Deeds Stamp & File Number					
4.	Lot No, Reco	rded Plat			A B	C D E	FG	<u> </u>	jκ		
IJ,	One quarter corner, Sections			,	2 - 6 -	 	+	-\$	1	- -	
ı,	John R. Garske , in a hereby certify that under requirem	i field survey on	July 3	96	4 - 7 -		_ <u>i</u>	-10	-11	-12-	
in I ma Ma 5 a De	hereby certify that under required lines 1 and 2 above were in conformation of survey instructions of an agement or by a decree of a Coabove were in conformance with acree of a Court of Law; established expressed below:	rmance with regulations and the United States Departr ourt of Law and/or that the c the rules of the Michigan B	rules therefore as require ment of the Interior, Boorner points mentioned in loard of Professional Sur	ed in the current ureau of Land n lines 3, 4 and rveyors or by a	6 18-7 8 19- 9 10 30-	20-	21-28-	22	23 26 26	-24-	
NC	TF: Not more than 4 corners	all in the same town on	d range may be recor	dod	11		- - 	+-+-	+	┿	

Description of original monument and accessories and/or subsequent restoration:

Original survey by Austin Burt in 1851. He set a post with bearing trees: 16" yellow birch - S57°E - 27 links, 16" yellow birch -N67°W - 37 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I set the corner in the centerline of Johnson Road at the intersection of ancient fence lines running east and west. Measurements

north (2631.51') and south (2639.66') to known corners were used to verify this position.

Record research on file

on this certificate.

C. Description of monument for comer and accessories established to perpetuate locating the position of the corner:

I set a 5/8" x 30" rebar capped with a 3 1/4" diameter brass cap stamped: T47N, R46W, 1/4, S-28, S-27, 1996, R.L.S. 28410, from which I established the following bearing trees and reference objects:

Power pole - S22°W - 97.27 feet

14" basswood - due west - 57.64 feet

13" tamarack - N37°E - 39.09 feet

Reference monument consisting of a 2 1/2" diameter x 30" aluminum pipe capped with a 3 1/4" diameter aluminum cap stamped: County Remonumentation, T47N, R46W, R.M., 1/4, S-28, S-27, 1996, R.J.S. 28410, N41°W, 37.22 feet

6' steel rail with sign 1.22 feet away

Signed by Surveyor's Michigan License No. 28410 FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SUI

JOHN R garske

LAND SURVEYOR

28410

LAND