

# SURVEY & REMONUMENTATION

OCT 03 1996

## COMMISSION

### LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Gogebic  
(County)

Located In:

Corner Code #

- |   |   |     |   |     |      |
|---|---|-----|---|-----|------|
| 1. Public Land Survey                   | T | 47N | R | 46W | G-11 |
|   | T |     | R |     |      |
|   | T |     | R |     |      |
|   | T |     | R |     |      |
| 2. Property Controlling<br>in Section   | S |     | T | R   |      |
|   | S |     | T | R   |      |
| 3. Miscellaneous<br>Property in Section | S |     | T | R   |      |
|   | S |     | T | R   |      |

Register's Office }  
Gogebic County } ss.

Received for record the  
16<sup>TH</sup> day of August  
A. D. 1996 at 11:10 o'clock  
A m., and recorded in  
Liber 6 of CORNERS  
on page 20  
Ramona Collins Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Section corner common to Sections 27, 28, 33, 34, T47N, R46W.

I, John R. Garske, in a field survey on July 3, 1996,  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current  
manual of survey instructions of the United States Department of the Interior, Bureau of Land  
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and  
5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a  
Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found  
as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**


**A. Description of original monument and accessories and/or subsequent restoration:**

- Original survey by Austin Burt in 1851. He set a post with bearing trees: 8" yellow birch - S50°E - 12 links, 8" yellow birch - N38°W - 7 links.
- Undated notes from the Gogebic County Road Commission indicate corner at the road centerline with distances of 5270.2 north and 2656.7 west to other corners.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

I established the corner position at the centerline intersection of Johnson and Spruce Roads. This corner position of its well, North, south, east and west with fence lines. Measurements to monumented corners North(2639.66'), East(2622.06') and west(2662.91' m, 2656.7 R) were used to verify this centerline location.

Record Research on file.



**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- I set a 5/8" x 30" rebar capped with a 3 1/4" diameter brass cap stamped: T47N, R46W, 27, 28, 33, 34, 1996, R.L.S. 28410, from which I established the following bearing trees and reference objects:
- Power/light pole - N47°W - 47.70 feet
  - Power pole - N84°E - 164.28 feet
  - 12" red pine - S36°E - 54.39 feet
  - Reference monumentation, T47N, R46W, R.M., 28, 27, 33, 34, 1996, R.L.S. 28410, N55°E, 42.29 feet
  - 6' steel rail with sign 1.56 feet away

PEER GROUP APPROVED  
Richard P. Dehn 8/14/96  
COUNTY REPRESENTATIVE

Signed by John R. Garske

Date 8-4-96

Surveyor's Michigan License No. 28410