

SURVEY & REMONUMENTATION

JAN 22 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in
Gogebic
(County)

	Located In:	Corner Code #
1. Public Land Survey	Section 33, 47W, 46W	G-12
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

Received for record the
24th day of November
A. D. 1997 at 11:40 o'clock
A m., and recorded in
Liber 6 of CORNERS
on page 268
Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1/4 corner sections 33 & 34, T47N, R46W

I, John R. Garske, in a field survey on November 6, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by Austin Burt, D.S. in 1851. He set a wood post from which:
Y. Birch 18" S57°W 19 links
Fir 6" N67°E 5 links
3.37 ch. south of corner- foot of ledge (222.42') 1/4 cor. set @ 40.12 chains.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I set the corner at the centerline intersection of ancient fence lines west and east with an old N-S road now overgrown. The centerline of the road is 16.5' (1 rod) east of an old rock fence with barbwire & posts on the south edge. The fence line picks up again on the east side of Johnson Road. This corner location checks with the GLO call south 222' to foot of rock ledge.

(Research on file)

PEEB GROUP APPROVED
Richard P. Deahn 11/11/97
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I set a 2 1/2" dia. x 30" long alum. pipe with a 3 1/4" dia. alum. cap stamped to identify the corner, from which I established:

10" Balsam	S12°W	27.90 feet
6" Birch	S65°W	14.71 feet
6" Red Pine	N48°W	33.69
Steel Sign Rail	N21°E	3.24 feet

Signed by John R. Garske
Surveyor's Michigan License No. 28410

Date 11/11/97 No. 28410

