

**SURVEY & REMONUMENTATION**

OCT 13 1996

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

Register's Office }  
 Gogebic County } 88.

For corners in Gogebic  
 (County)

Located In:

Corner Code #

|                                      |                         |       |
|--------------------------------------|-------------------------|-------|
| 1. Public Land Survey Section 22     | T 47N R 46W             | H-9   |
|                                      | T _____ R _____         | _____ |
|                                      | T _____ R _____         | _____ |
|                                      | T _____ R _____         | _____ |
| 2. Property Controlling In Section   | S _____ T _____ R _____ | _____ |
|                                      | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Section | S _____ T _____ R _____ | _____ |
|                                      | S _____ T _____ R _____ | _____ |

Received for record the  
16<sup>th</sup> day of August  
 A. D. 1996 at 11:10 o'clock  
A m., and recorded in  
Lib 6 of CORNERS  
page 21  
Ramona Collins, Deputy  
 Register of Deeds  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

One quarter corner, Sections 22 and 27, T47N, R46W.

I, John R. Garske, in a field survey on July 3, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

| A  | B  | C  | D  | E  | F  | G  | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  |    |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |

**A. Description of original monument and accessories and/or subsequent restoration:**

Original survey by Austin Burt in 1851. He set a post with bearing trees: 24" sugar - S5°W - 21 links (13.86') and a 7" Ironwood - N34°W - 14 links (9.24').

-Old undated notes from the Gogebic County Road Commission indicate a corner at the centerline intersection.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

I established the corner position at the centerline intersection of Harding and Elder Roads. The corner also lies in the centerline of an old trail running north. Measurements east (2625.50') and west (2641.25') were used to verify this position.

2638.23  
926

Record Research on file.



**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

I replaced the set P.K. nail with a stamped brass cap from which I established the following reference objects:

- Power pole - S50°E - 46.04 feet
- 7" ash - N60°E - 52.05 feet
- 5" oak - N32°W - 41.64 feet

Reference monument consisting of a 2 1/2" diameter x 30" aluminum pipe with a 3 1/4" diameter aluminum cap stamped: County Remonumentation, T47N, R46W, S-22, S-27, R.M., 1/4, 1996, R.L.S. 28410, N60°E, 49.08 feet.

Set a steel rail with sign 1.21 feet away.

PEER GROUP APPROVAL  
Richard L. Neuman 8/14/96  
 COUNTY REPRESENTATIVE

Signed by John R. Garske  
 Surveyor's Michigan License No. 28410

Date 8-4-96