

SURVEY & REMONUMENTATION

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Gogebic (County)	Located In:	Corner Code #
1. Public Land Survey Section 3	T 47N R 46W	I-1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register's Office }
 Gogebic County } ss.

Received for record the
30th day of DECEMBER
 A. D. 1993 at 12:30 o'clock
P m., and recorded in
 Liber 4 of CORNERS
 on page 342
Betty Marie Deputy
 Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Section corner common to S-2 & S-3, T47N, R46W and
 S-34 & S-35, T48N, R46W.

I, John R. Garske, in a field survey on December 27, 1993,
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
 in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
 current manual of survey instructions of the United States Department of the Interior, Bureau of Land
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
 Court of Law; established, re-established, monumented, re-monumented, recovered, found as
 expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
 on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Survey by William A. Burt on September 9, 1847. Set sugar post from which a 20" sugar bears -
 N62°E - 34 links and an 8" hemlock bears N57°W - 29 links and a 10" sugar bears S65°W - 19
 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence found. Found a 6" nail at the intersection of a two-track road to north and an
 old North-South fence line to the south and at the center line of Stone Road. This corner position
 has been used in several surveys and is generally accepted as the most probable location of the
 original section corner by both local surveyors and area residents. Due to the history of the corner
 location and its general use and acceptance, I am accepting it as marking the true section corner
 location.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced the nail with a 3/4" x 30" iron rod with a stamped 3 1/2" diameter aluminum cap from
 which I established the following bearing trees and reference objects:

- 18" apple - S39°E - 40.36 feet
- 5" basswood - N19°W - 34.40 feet
- Reference monument - N25°E - 34.89 feet. Set 2 1/2" x 30" aluminum County Monument
 with a 3 1/2" stamped aluminum cap - steel sign post - 1.33 feet.
- Reference monument - S57°W - 47.78 feet. Set 2 1/2" x 30" aluminum County Monument
 with a 3 1/2" stamped cap - steel sign post - 1.96 feet.

Signed by John R. Garske Date 12/29/93
 Surveyor's Michigan License No. 28410