

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Gogebic  
 (County)

Located In:

Corner Code #

- |                                    |                           |            |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey              | T <u>47N</u> R <u>46W</u> | <u>I-2</u> |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

**One-quarter corner common to S-2 & S-3, T47N, R46W.**

I, John R. Garske, in a field survey on December 28, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

**Survey by Austin Burt on June 10, 1851. Set wood post from which a 12" elm bears south - 11 links and a 14" Y. birch bears N20°W, 5 links.**

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

**No original evidence found due to road and utility construction. I found a 6" spike at corner position at the intersection of East-West roads and an old North-South fence line. This corner position has been used and accepted in several surveys and is generally accepted by local residents as marking the one-quarter corner.**

**Research on file with County Register of Deeds Office.**

**PEER GROUP**

**Approved**

Richard P. Debra

9/14/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**Set a 3/4" x 30" rebar with a 3 1/2" stamped aluminum county cap. Established the following bearing trees and reference objects:**

**5" ash - S44°E - 78.51 feet.**

**Reference monument - S55°W - 35.75 feet. Set 2 1/2" x 30" aluminum County Monument with a 3 1/2" stamped aluminum cap - steel sign post - 1.67 feet.**


**Reference monument - north - 23.40 feet. Set 2 1/2" x 30" aluminum County Monument with a 3 1/2" stamped aluminum cap - steel sign post - 1.29 feet.**

Signed by

John R. Garske

Date

Surveyor's Michigan License No. 28410



Register's Office }  
 Gogebic County } ss.

Received for record the  
16<sup>th</sup> day of SEPTEMBER  
 A. D. 1994 at 3:20 o'clock  
P m., and recorded in  
 Liber 5 of CORNERS  
 on page 99  
Ramona Collins Dep.  
 Register of Deeds

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							