

SURVEY &  
REMONUMENTATION

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County } ss.

Received for record the  
30<sup>th</sup> day of DECEMBER  
A. D. 1993 at 12:20 o'clock  
P m., and recorded in  
Liber 4 of CORNERS  
on page 325  
*Betty Harris, Deputy*  
Register of Deeds

Register of Deeds Stamp & File Number

For corners in

Gogebic  
(County)

Located In:

Corner Code #/

- |                                       |                           |            |
|---------------------------------------|---------------------------|------------|
| 1. Public Land Survey                 | T <u>47N</u> R <u>46W</u> | <u>I-3</u> |
|                                       | T _____ R _____           | _____      |
|                                       | T _____ R _____           | _____      |
|                                       | T _____ R _____           | _____      |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____   | _____      |
|                                       | S _____ T _____ R _____   | _____      |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____   | _____      |
|                                       | S _____ T _____ R _____   | _____      |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Section corner S-2, 3, 10 & 11, T47N, R46W.

I, John R. Garske, in a field survey on December 13, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Survey by Austin Burt, U.S.D.S, on June 10, 1851. Set wood post from which a 10" fir bears S85°W, 5 links and a 14" fir N48°E, 22 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original bearing trees found. Found a 5/8" iron rod at the corner location. The corner position was located by use of ancient fence links north, south and west and checking with natural feature ties from the original survey notes. This corner position has been used in several surveys of record by several surveyors. The corner falls in the intersection of an old N-S and E-W trail very overgrown.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found a 5/8" x 30" capped rebar and set 3 1/2" aluminum cap stamped: County Remonumentation; T47N, R46W; S-3; S-2; S-10; S-11; 1993; RLS 28410. Established the following bearing trees and reference objects:

- P. pole #2-6/04 - N72°E - 59.08 feet
- 10" ash - N43°W - 21.70 feet
- 12" oak - S42°E - 36.44 feet
- Steel sign post - north - 5.40 feet

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3									●				
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Signed by John R. Garske  
Surveyor's Michigan License No. 28410

Date 12/20/93

