

SURVEY &
 MONUMENTATION
 COMMISSION
 APR 07 1995

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corner in _____
 Gogebic (County)

Located in: _____ Corner Code # _____

1. Public Land Survey Section 11	T 47N R 46W	I-4
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

1/4 cor. comm. to sec's. 10 & 11

Register's Office }
 Gogebic County } ss.
 Received for record the
21st day of OCTOBER
 A. D. 1994 at 11:15 o'clock
A m., and recorded in
 Liber 5 of CORNERS
 on page 152
Ramona Collins Deputy
 Register of Deeds
 Register of Deeds Stamp & File Number

I, John P. Goss, in a field survey on September 16, 1994,
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
 in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
 current manual of survey instructions of the United States Department of the Interior, Bureau of Land
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
 Court of Law; established, re-established, monumented, re-monumented, recovered, found as
 expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by Austin Burt, in 1851. Set post. Original bearing trees.
 Lynn 6" S61°W 35 links & Sugar 7" N44°E 27 links.

1978 survey found 1" iron pin as called for in plat of East End Addition and recorded in Liber 1 of Land Corners, Page 400. Accessories: P. Pole-S38°E-30.37'; Guy Pole-N33°E-25.63'; P. Pole-N46°W-32.14'. By Ewart C. Muller, RLS 15408 and John P. Goss, RLS. 23509.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found a P.K. Nail marking the corner position and checked with some of muller's and Goss's witness in thier certificate. I updated the corner monument and accessories as noted below to state and county specifications.

Act 74 research on file with the County Register of Deeds Office.

PEER GROUP **Approved**
Richard L. Deahn 10/12/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A P.K. nail marks the corner position from which I established the following bearing objects.

I set reference monuments #1 and #2 consisting of 2 1/2" diameter x 30" long aluminum pipe with 3/4" diameter cap stamped to note the corner position as follows:

- | | | | |
|-------------------------------|-------|--------|-------------------------|
| R.M. #1 | N54°E | 13.26' | - steel sign post-1.15' |
| R.M. #2 | N62°W | 42.56' | - steel sign post-0.87' |
| D.H. nail in P. Pole | S30°E | 28.90' | |
| Center of top nut of Fire Hyd | S42°W | 42.54' | |

Signed by John P Goss Date 9-24-94
 Surveyor's Michigan License No. P.S. 23509

