

SURVEY & REMONUMENTATION
APR 07 1995
COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
 Gogebic County } ss.

Received for record the
4th day of NOVEMBER
 A. D. 1994 at 9:25 o'clock
A m., and recorded in
 Liber 5 of COGNAC
 on page 160

Ramona Collins Deputy
 Register of Deeds

Register of Deeds Stamp & File Number

For corners in Gogebic (County) Located In: _____ Corner Code # _____

1. Public Land Survey Section 10	T <u>47N</u> R <u>46W</u>	<u>I-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Sec. Cor. comm. to Sec's. 10,11,14 & 15

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, John P. Goss, in a field survey on October 16, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 Original survey by Austin Burt in 1851. Set a post.

Original bearing trees: Fir-16"-S72°E-22 links; Hemlock 12"-N35°W-35 links

In 1983 John P. Goss found 1" sq. iron bar marked with 10,11,14 & 15 on opposite sides. It was recorded in Liber 2 of Land Corners on page 430 and 431 by John P. Goss the following accessories: 10" Elm-Due North-2.39'; 20" Wild cherry-S88°W-19.55'; 6" Apple-S50°E-19.60'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found a 1" sq. iron bar as marked in Liber 2 of Land Corners pages 430 and 431. This checked with stumps of witnesses trees. I did upgrade the accessories as noted below to State and County specifications.

Act 74 research on file with County Register of Deeds Office.

FEER GROUP Approved
Richard L. Dehn 11/3/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I set a 2½" x 30" long aluminum pipe with a 3½" aluminum cap stamped: S-10, S-11, S-14, S-15, T.47 N., R.46 W., 1994, P.S. 23509 over the 1" sq. iron bar that I found. I established the following bearing trees and reference objects.

D.H. nail and bottle cap in 10" poplar	N 17° W	44.61'
D.H. nail and bottle cap in 6" poplar	N 83° E	25.37'
D.H. nail and bottle cap in 15" poplar	S 11° W	70.97'
D.H. nail and tag in 5" Ash	S 44° E	31.15'



Signed by John P. Goss
 Surveyor's Michigan License No. P.S. 23509

Date 10-22-94