

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
 Gogebic County } ss.

Received for record the
14TH day of AUGUST
 A. D. 1995 at 10:10 o'clock
P m., and recorded in
 Liber 5 of CORNERS
 on page 291
Ramona Collins, Deputy
 Register of Deeds

For corners in Gogebic (County) Located In: Corner Code #

1. Public Land Survey S-14	T <u>47N</u> R <u>46W</u>	<u>I-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

1/4 cor. comm. to sec's 14 & 15

I, John P. Goss, in a field survey on July 23, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt in June 1851. Set post.
 Original bearing trees:

John P. Goss in 1981 using the Plat of Plam's found a 1" iron pin in 12" sq. concrete monument. Accepted same as corner and recorded it in Liber 2 on pages 112 & 113 of Land Corners for Gogebic County: 13" Maple- N 01° W-58.00'; 8" Maple- S 50° W- 10.93'; 6" Poplar- N 40° W- 22.86'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found the the 1" iron pin in concrete monument as called for in John P. Goss certification and it checked with two (2) bearing trees. I updated the corner monument and accessories as noted below to state and county specification.

Act 74 reseach on file with the County Register of Deeds Office.

PEER GROUP APPROVED
Richard P. Deahn 8/2/95
 COUNTY MICHIGAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

The Corner position is marked by the 1" iron pin in the 12" sq. concrete monument. I established the following bearing trees and objects. Two reference monument consisting of a 2 1/2" x 30" aluminum pipe with a 3 1/4" aluminum cap stamped to indicate the corner position as follows:

R.M.	N 52° E	7.68'	with 6' steel rail & sign--1.08'
R.M.	S 60° E	13.15'	with 6' steel rail & sign- 1.30'
11" Maple	S 50° W	10.93'	
6" Poplar	N 58° W	35.28'	



Signed by John P. Goss Date July 27, 1995

Surveyor's Michigan License No. R.S. 23509

Fed. No. L-17