

SURVEY & REMONUMENTATION

JAN 22 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office } ss.
Gogetic County }

For corners in
Gogetic

Located In: Corner Code #

Section 22	47N	46W	I-8
1. Public Land Survey	T	R	
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

Received for record the
2nd day of DECEMBER
A. D. 1997 at 10:35 o'clock
10 m., and recorded in
Liber 6 of GOGETIC
on page 281
Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____
1/4 corner section 22 & 23, T47N, R46W

John R. Garske November 7, 1997

I, _____, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by Austin Burt, D.S. on June 12, 1851. He set a wood post from which:
B. Oak 36" S68°W 20 links
Elm 14" N47°E 25 links
Descend Hill 60' - 3.86 chains north.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I set the corner at the intersection of ancient fence lines running east, west and north. A blue line extends south from this position. No evidence of the original corner exists. This position checks with the descend hill call north. The fence line intersection is the best evidence available of the original corner location.

(Research on file)

PEER GROUP APPROVED
Richard L. Deahn 12/1/97
COUNTY REGISTER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I set a 2 1/2" dia. x 30" long alum. pipe with a 3 1/4" dia. alum. cap stamped to identify the corner, from which:
6" Sugar N53°E 3.09 feet
5" Sugar S13°E 14.61 feet
9" Basswood S54°W 8.65 feet
5" Sugar N37°W 18.79 feet
Steel Sign Post SELY 0.91 feet

Signed by John R. Garske
Surveyor's Michigan License No. 28410

Date 11/2/97 No. 28410

