

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

Register's Office }  
 Gogebic County } **SE**

Received for record the  
21<sup>st</sup> day of JULY  
 A. D. 1995 at 1:35 o'clock  
P m., and recorded in  
 Liber 5 of CORNERS  
 on page 266  
Ramona Collins, Deputy  
 Register of Deeds

Register of Deeds Stamp & File Number

For corners in  
Gogebic  
(County)

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey Sec. 2 T 47N R 46W J-3  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_  
1/4 cor. comm. to sec's. 2 & 11

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3										●			
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John P. Goss, in a field survey on July 14, 1995  
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
 in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
 current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
 Court of Law; established, re-established, monumented, re-monumented, recovered, found as  
 expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
 Original corner established by Austin Burt in June 1851. Set post.  
 Original bearing trees: Lynn 7" S 35° W 5 links  
 Elm 7" N 40° E 16 links

John P. Goss in 1983 found 1" iron pin marker 2 on one side and 11 on the other side and recorded this corner in Liber 2 page 314 and 315 of Land Corners for Gogebic County. He established the following witnesses and distances: 27" Maple- N 87° W- 20.95'; 6" Maple- Due N. - 16.88'; 6" Maple- S 22° E- 15.10'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 I found the 1" iron pin at the corner position and it checked with John P. Goss certification. I updated the corner monument and accessories as noted below to state and county specification.

Act 74 reseach on file with the County Register of Deeds Office.

**PEER GROUP APPROVED**  
Richard R. Dredman 7/18/95  
 COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 I placed a 2½" x 30" aluminum pipe with a 3½" cap stamped as follows:  
 County Remonumentation; T.47 N., R.46 W.; 1/4; S-2, S-11, 1995; P.S. 23509.  
 I established the following bearing trees and reference objects.

- D.H. Nail & tag in 30" Maple N 87° W 20.95'
- D.H. Nail & tag in 10" Maple N 86° E 47.60'
- D.H. Nail & tag in 8" Maple S 22° E 15.10'
- 6' steel rail and sign N 32° W 1.89'



Signed by John P Goss Date July 15, 1995  
 Surveyor's Michigan License No. P.S. 23509

Fed. No. E-19  
 266