

SURVEY & REMONUMENTATION

JAN 22 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office } ss.
Gogebic county }

For corners in
Gogebic
(County)

	Located In:	Corner Code #
1. Public Land Survey	Section 23 47N 46W J-7	
	T R	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Received for record the
2ND day of DECEMBER
A. D. 1997 at 10:35 o'clock
A m., and recorded in
Liber 6 of CORNERS
on page 282
Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1/4 corner section 14 & 23, T47N, R46W

I, John R. Garske, in a field survey on November 11, 1997 hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by Austin Burt, D.S. on June 19, 1851. He set a wood post from which:
Yellow Birch 18" S 28°W 19 links
Yellow Birch 10" N 24°W 26 links
Stream - 8 links - 4.64 chains east (306.24 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I established the corner position in the center of an old overgrown trail which has been cut through a rock hill approximately 8' high. An ancient post and barbwire fence runs east and west, from this location which is at the centerline of Koski Road extended. A blue paint line runs north. The distance north to the monumented center of section in the Plat of Anvil checks relatively well.

PEER GROUP APPROVED

Richard P. Decker 12/1/97
COUNTY BARRETT

(Research on file)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I set a 3/4" x 30" iron rod with a 3 1/4" dia. alum. cap stamped to identify the corner from which:
6" Maple N86°W 35.78 feet
3" Ironwood N40°E 11.02 feet
4" Oak S36°E 9.47 Feet
Steel Sign Rail S03°E 21.70 feet

Signed by John R. Garske
Surveyor's Michigan License No. 28410

Date 11/26/97

