

Register's Office }
Gogebic County } ss.

Received for record the
14TH day of AUGUST
A. D. 1995 at 10:10 o'clock
A m., and recorded in
Liber 5 of CORNERS
on page 288
Ramona Collins, Deputy
Register of Deeds

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Gogebic

(County)

Located in:

Corner Code #

- | | | | |
|---------------------------------------|-------------------------|--------------------|-------------|
| 1. Public Land Survey | | <u>T 47N R 46W</u> | <u>K-1</u> |
| | | <u>T 48N R 46</u> | <u>K-13</u> |
| | | T _____ R _____ | _____ |
| | | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ | _____ |
| | S _____ T _____ R _____ | _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ | _____ |
| | S _____ T _____ R _____ | _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | | |
| 5. Private Claims _____ | | | |

Register of Deeds Stamp & File Number

Sec. cor. comm. to Sec's. 1 & 2, T.47 N., R.46W
and 35 & 36, T.48 N., R.46 W.

John P. Goss in a field survey on July 30, 1995

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by William A. Burt. Set sugar post.
Original bearing trees: Hemlock 16" N 65° E 52 links
Hemlock 20" N 27° W 28 links

John R. Garske re-established this corner in 1991. He recorded it in Liber 4 page 51 of Land Corners for Gogebic County. He established the following witnesses and distances. 6" Maple- S 54° W- 90.45'; 14" Maple S 75° E- 111.45'; 14" Maple S 41° E- 104.42. He set a 3/4 inch diameter by 4 foot long iron rod with plastic cap at the Section corner location.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I did not find the 3/4" by 4' iron rod. I found the three (3) witnesses trees, which checked out to one location. I updated the Corner monument and accessories as noted below to state and county specification.

Act 74 reseach on file with the County Register of Deeds Office.

Richard L. Braden 8/10/95
COUNTY REGISTER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I set a 2 1/2" by 30" aluminum pipe with a 3 1/2" aluminum cap stamped as follows at location of corner: County Remonumentation; T.47-48 N, R.46 W.; S-1, S-2, S-35 and S-36; 1995, P.S. 23509. I established the following bearing trees and reference objects.

7" Maple	S 54° W	90.45'
14" Maple	S 75° E	111.45'
16" Basswood	S 41° E	104.42'
26" Hemlock	N 58° W	124.45'



Signed by John P. Goss

Date July 31, 1995

Surveyor's Michigan License No. P.S. 23509

Fed. No. A-21