

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
 Gogebic County } ss.

Received for record the
12TH day of MAY
 A. D. 1995 at 11:20 o'clock
A m., and recorded in
 Liber 5 of CORNERS
 on page 255
Ramona Collins Deputy
 Register of Deeds

Register of Deeds Stamp & File Number

For corners in

Gogebic
 (County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|---------------------------|------------|
| 1. Public Land Survey | T <u>47N</u> R <u>46W</u> | <u>K-2</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

1/4 cor. comm. to sec's. 1 & 2

I, John P. Goss, in a field survey on April 23, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original Survey by Austin Burt, D.S. on June 10, 1851. Set post.
 Original Bearing Trees: Sugar 12"-S82°W-25 links; Y.Birch 12"- N 76°E- 15 links.

John R. Garske in 1989 found a 1½" iron pipe located at corner, approximately 8" below surface of gravel roadway. He recorded it in Liber 3 page 284 of Land Corner for Gogebic County: 6" Aspen- N 62°E-66.24'; 6" Maple clump- N 68° W- 32.76'; Power Pole- S 37° W- 39.06'; all corners have D.H. Nail/ cap.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found the iron pipe marking the corner position buried about 8 inches and it checked with the three (3) bearing objects in John R. Garske certification. I updated the corner monument and accessories as noted below to state and county specification.

Act 74 reseach on file with the County Register of Deeds Office.

PEER GROUP APPROVED


Richard L. Walsh 5/11/95
 COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I set a 5/8" x 24" rebar next to the iron pipe with a 3¼" aluminum cap 6" below the road surface stamped: County Remonumentation; S-1; S-2; T.47 N.; R.46 W.; 1/4; 1995; P.S. 23509. I established the following bearing trees and reference objects.

D.H. Nail & Cap in 8" Aspen	N 62° E	66.24'
D.H. Nail & Cap in 9" Maple clump	N 68° W	32.76'
D.H. Nail & cap in Power Pole	S 37° W	39.06'

reference monument consisting of a 2½" x 30" aluminum monument with a 3¼" aluminum cap stamped to indicate corner position: S 54° E- 47.41 with a 6' Steel Rail and sign- 1.00'.



Signed by John P Goss

Date April 23, 1995

Surveyor's Michigan License No. P.S. 23509

Fed. No. C-21