

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office } ss.
 Gogebic County }

Received for record the
21st day of July
 A. D. 1995 at 1:35 o'clock
P m., and recorded in
 Liber 5 of CORNERS
 on page 267
Harmona Collins, Deputy
 Register of Deeds

For corners in

Gogebic
 (County)

Located in:

Corner Code #

- | | | |
|---------------------------------------|---------------------------|------------|
| 1. Public Land Survey | T <u>47N</u> R <u>46W</u> | <u>K-3</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Register of Deeds Stamp & File Number

Sec. Cor. Comm. to Sec's. 1,2,11 & 12

I, John P. Goss, in a field survey on May 12, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt on June 10, 1851. Set post. Original bearing trees:

Aspen 12" S 38° E 17 links
 Aspen 8" N 18° W 36 links

In 1983 John P. Goss found a 1/2" rebar using MDOT plans and recorded this corner in Liber 2 on page 490 of Land Corners for Gogebic County. Established the following witnesses and distances: P.Pole-N 55° E-38.17'; Face side of stop sign post- S 65° W- 37.45'; NE corner of garage- N 19° W- 93.73'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found the 1/2 inch rebar marking the corner position and it checked with the witnesses in John P. Goss certification. I updated the corner monument and accessories as noted below to state and county specification.

Act 74 research on file with the County Register of Deeds Office.

PEER GROUP APPROVED
Richard R. Neal 7/10/95
 COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set a 2 1/2" brass cap with a 2" stem at 1" below asphalt road surface. Cap is stamed: T47N, R46W; S-1, S-2, S-11, S-12; 1995; P.S. 23509. I established the following bearing trees and reference objects.

P.Pole N 55° E 38.17'
 4" Elm S 43° W 63.59'
 5" Apple N 33° W 59.68'

Reference Monument consisting of a 2 1/2" x 30" aluminum monument with a 3 1/4" aluminum cap stamped to indicate corner position - S 29° E- 59.01' with a 6' steel rail and sign at 1.49'.



Signed by John P Goss

Date May 13, 1995

Surveyor's Michigan License No. P.S. 23509

Fed. No. E - 21