

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
 Gogebic County } ss.

For corners in
Gogebic
 (County)

Located In: _____ Corner Code # _____

Received for record the
21st day of JULY
 A. D. 1995 at 1:40 o'clock
P m., and recorded in
 Liber 5 of CORNERS

on page 271
Ramona Collins Deputy
 Register of Deeds

Register of Deeds Stamp & File Number

- | | | |
|-------------------------|-----------------------------------|------------|
| 1. Public Land Survey | Sec. 11 T <u>47N</u> R <u>46N</u> | <u>K-4</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling | S _____ T _____ R _____ | _____ |
| in Section | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous | S _____ T _____ R _____ | _____ |
| Property in Sec. | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

1/4 Cor. comm. to Sec's. 11 & 12

I, John P. Goss, in a field survey on May 12, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt on June 10, 1851. Set post.
 Original bearing trees:

W. Pine 6" S 81° E 8 links
 Fir 10" N 48° W 11 links

In 1983 John P. Goss using MDOT plans recorded this corner in Liber 2 on page 490 of Land Corners for Gogebic County; Established the following distances and witnesses: T.Pole- N 60° W- 33.84'; P.Pole-N 45° E- 36.74'; center of Post for Street sign- S 18° E- 44.35'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found the 1/2 inch rebar marking the corner position and it checked with the witnesses in John P. Goss certification. I updated the corner monument and accessories as noted below to state and county specification.

Act 74 reseach on file with the County Register of deeds Office.

PEER GROUP APPROVED

Richard P. Deahn 7/18/95
 COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

set a 2 1/2" brass Cap with a 2" stem at 1" below asphalt road surface. Cap is stamped T47N, R46W; 1/4; S-11, S-12; 1995; P.S. 23509. I established the following bearing trees and reference objects.

T. Pole- N 60° W - 33.84'
 P.Pole - N 45° E - 36.64'
 5" Spruce- S 51° E- 52.79'
 Reference Monument consisting of 2 1/2"x30" aluminum monument with a 3 1/4" Alumina cap stamped to indicate the corner position.
 S 88° W- 36.00'.



Signed by John P Goss Date May 13, 1995

Surveyor's Michigan License No. P.S. 23509
 Fed. No. G- 21