

SURVEY & REMONUMENTATION

JAN 22 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Gogebic

(County)

Located In:

Corner Code #

1. Public Land Survey

Section 13 47W 46W K-7

T	R	_____	
T	R	_____	
T	R	_____	
T	R	_____	
S	T	R	_____
S	T	R	_____
S	T	R	_____
S	T	R	_____

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Section corner to 13, 14, 23 & 24, T47N, R46W

John R. Garske October 23, 97

I, _____, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by Austin Burt, D.S. in 1851. He set a wood post from which:
 Sugar 6" S48°W 1 5links
 Sugar 8" N75°E 35 links
 1.5 chains west - "run"
 2.00 chains west - S.E. side of knob

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

At the corner location I found a 1 1/4" "O.D. iron pipe at the intersection of ancient fence lines running east-west and south. I measured 33 feet west to a small drainage course and 132 feet west to side of knob which checks extremely good with GLO calls noted above. I accepted the iron pipe at the fence intersection as the best evidence of the original corner position.

(Research on file)

PEER GROUP APPROVED
Richard R. Deakin 11/11/97
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I set a 2 1/2" dia. x 30" long alum. pipe with a 3 1/4" dia. alum. cap stamped to identify the corner, from which I established:

8" S. Maple	N80°W	22.75 feet
8" S. Maple	N52°E	21.79 feet
10" S. Maple	S32°E	24.89 feet
Steel Sign Rail	S36°W	1.47 feet

Signed by *John R. Garske*
 Surveyor's Michigan License No. 28410

Date 11/11/97



Register's Office }
 Gogebic County } ss.

Received for record the
24th day of NOVEMBER
 A. D. 1997 at 11:40 o'clock
A m., and recorded in
 Liber 6 of CORNER
 on page 271
Ramona Collins, Deputy
 Register of Deeds

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		16		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													