

**SURVEY & REMONUMENTATION**

**JAN 22 1998**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County } ss.

Received for record the  
24<sup>TH</sup> day of NOVEMBER  
A. D. 1997 at 11:40 o'clock  
A m., and recorded in  
Liber 6 of CORNERS  
page 272  
Ramona Collins, Deputy  
Register of Deeds

For corners in	Located In:	Corner Code #
<u>Gogebic</u>		
(County)		
1. Public Land Survey	Section 23, <u>47W</u> 46W	K-9
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_  
Section corner to 23, 24, 25 & 26, T47N, R46W

I, John R. Garske, in a field survey on November 6, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	10		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by Austin Burt, D.S. in 1851. He set a wood post from which:  
Y. Birch 16" S63°W 41 links  
Fir 12" N45°E 30 links  
1935 - USDA form 874-9 by L. Barron notes corner recovered as an original GLO corner consisting of a 30" high cedar stake. They set a metal poster on S. Side of a post 25' to corner. ~~The corner.~~ The corner was revisited (no date) with the poster found on a new road grade.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

At the corner position I found a fence line running north and west with a rusty poster on a post at the intersection. Blue lines run in all four directions from this post, which is on the west edge of an old N-S trail. The fence line also picks up again 1320± east and extends to River Road. I am accepting this fence intersection as the best evidence to reestablish the corner. I believe the post I found was the 1935 post reset at the present corner location. Retracement measurements west 15.27 chs. (1007.82') and North, 27.50 chs. (1815') to the Black River check reasonably well.

(Research on file)

**PEER GROUP APPROVED**  
Richard P. Dzahn 11/11/97  
**COUNTY REPRESENTATIVE**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position, I set a 2 1/2" dia. x 30" long alum. pipe with a 3 1/4" dia. alum. cap stamped to identify the corner from which I established:

5" S. Maple	N76°E	6.57 feet
5" Balsam	S38°W	13.94 feet
7" S. Maple(triple)	N87°W	12.54 feet
Steel Sign Rail	S04°E	2.49 feet

Signed by John R Garske  
Surveyor's Michigan License No. 28410

Date 11/11/97

