

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

Register's Office }  
 Gogebic County } ss.

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>47N</u> R <u>46W</u>	<u>L-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Received for record the  
19<sup>th</sup> day of OCTOBER  
 A. D. 1995 at 10:10 o'clock  
A m., and recorded in  
 Liber 5 of CORNEES

on page 299  
Lamona Collins Deputy  
 Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_  
 One-quarter corner common to Sections 1 and 12, T47N, R46W.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, John R. Garske, in a field survey on October 11, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Survey by Austin Burt on June 10, 1851. Set wood post from which a 10" hemlock bears S09°E - 42 links and an 8" fir bears N24°W - 38 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence found due to logging activity. Found a 2 1/4" O.D. iron pipe - N05°E, 10.86 feet from the corner location. Probably set by Gunner Lorenson, Forester in Work around the Blackjack Ski area. I did not accept. Corner set by single proportionate method on line and one-half the distance between opposing section corners in accordance with the original government notes. Old fence lines run east and south from our corner position.

(Record research on file.)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set a 2 1/4" x 30" aluminum pipe with a stamped 3 1/4" aluminum cap from which I established the following bearing trees and reference objects:

- 4" B. ash - N37°W - 34.75 feet
- 12" tamarack - S50°W - 16.91 feet
- 10" spruce - S57°E - 47.90 feet
- Steel sign post - due south - 0.90 feet

PEER GROUP APPROVED  
Richard P. D. Zahn 10/12/95  
 COUNTY REPRESENTATIVE



Signed by John R. Garske Date 10-12-95  
 Surveyor's Michigan License No. 28410