

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
 Gogebic County } ss.

Received for record the
21ST day of SEPTEMBER
 A. D. 1995 at 9:55 o'clock
A m., and recorded in
 Liber 5 of CORNERS
 on page 296
Reimona Collins Deputy
 Register of Deeds

Register of Deeds Stamp & File Number

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #:
1. Public Land Survey	T <u>47N</u> R <u>46W</u>	<u>L-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____
 One quarter corner common to Sections 12 & 13, T47N, R46W

I, John R. Garske, in a field survey on September 18, 19 95,
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
 in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
 current manual of survey instructions of the United States Department of the Interior, Bureau of Land
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
 Court of Law; established, re-established, monumented, re-monumented, recovered, found as
 expressed below.

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
 on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

On June 19, 1851, Austin Burt set a post from which a 14" cedar bears S48°W, 10 links and a 10" cedar - N45°E, 9 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original or subsequent corner evidence can be found due to mining activity.

I reestablished the corner position by retracing the section line shown on Supervisor's Plat No. 2 and No. 3. This line shows a distance of 1311.02 feet from the section corner common to Sections 12, 13, 7, and 18 to the east one-sixteenth corner common to Section 12 and 13. Plat monuments within said plats were found and checked to be accurate. I extended the monumented plat line to the one-quarter corner position. Corner position falls on the west slope of an old mine tailings pile. See sketch on back.


Record research form on file with Register of Deeds.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I set a 4 foot section of marsh rod with a 3 1/4" diameter aluminum cap stamped: County Remonumentation; 1/4; S-12; S-13; T47N, R46W; 1995; RLS 28410, from which I established the following bearing trees and/or reference object:

- 5" aspen - N75°E - 16.49 feet (slope distance)
- 3" cherry - Due West - 5.81 feet
- 3" cherry - N19°W - 27.48 feet (slope distance)
- Steel sign rail - S52°W - 1.08 feet

PEER GROUP APPROVED
Richard R. Dicks 9/15/95
 COUNTY REPRESENTATIVE



Signed by John R. Garske
 Surveyor's Michigan License No. 28410

Date 9-19-95

