

**SURVEY &
REMONUMENTATION**

OCT 03 1996

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

COMMISSION

For corners in
Gogebic
(County)

Located In:

Corner Code #

- | | | | |
|---|-------|-------|-----|
| 1. Public Land Survey | T 47N | R 46W | I-7 |
| | T | R | |
| | T | R | |
| | T | R | |
| 2. Property Controlling
in Section | S | T | R |
| | S | T | R |
| 3. Miscellaneous
Property in Section | S | T | R |
| | S | T | R |

Received for record the
16th day of AUGUST
A. D. 1996 at 11:10 o'clock
A. M., and recorded in
Liber 6 of CORNERS
on page 25
Ramona Collins Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

One-quarter section corner common to Sections 13 & 24, T47N, R46W.

I, John R. Garske, in a field survey on July 25, 1996
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current
manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and
5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a
Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found
as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- On June 9, 1851, Austin Burt, U.S. Deputy Surveyor, set a post with the following bearing trees:
16" Y. birch - N3°W - 33 links
12" Y. birch - S32°E - 17 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I established the corner at the centerline of River Road and Londo Road opposite an old fence line running west. Measurements east (2623.97') and south (5292.18') to known corner positions were used to verify this position. This corner location also checks well with dimensions shown on the Plat of The Village of Ramsay.

Record research on file.

PEER GROUP APPROVED
Richard P. Decker 8/14/96
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

The corner position is marked by a 3 1/4" diameter brass cap encased in concrete atop a 5/8" diameter x 24" rebar set 0.15' below bituminous surface. The cap is stamped: County Remonumentation, T47N, R46W, S-13, S-24, 1/4, 1996, RLS 28410. The following bearing tree and reference objects were established: 2 1/2" diameter x 30" aluminum pipe with a 3 1/4" aluminum cap stamped: County Remonumentation, T47N, R46W, R.M., S-13, S-24, 1/4, 1996, RLS 28410, S52°W - 38.24 feet with a steel sign rail 0.74' away.

- 12" Sugar - N65°W - 28.80 feet
- Lt. pole - S40°E - 46.56 feet
- Garage corner (concrete slab) - S40°W - 43.08 feet

Signed by John R. Garske
Surveyor's Michigan License No. 28410

Date 8-5-96



FORM APPROVED BY MICHIGAN BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983