

SURVEY & REMONUMENTATION

JAN 22 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Gogebic

(County)

Located In:

Corner Code #

1. Public Land Survey	Section 24	47N	46W	L-9
	T	R		
	T	R		
	T	R		
	T	R		
2. Property Controlling in Section	S	T	R	
	S	T	R	
3. Miscellaneous Property in Sec.	S	T	R	
	S	T	R	

Register's Office }
Gogebic County } ss.

Received for record the
2ND day of DECEMBER

A. D. 1997 at 10:55 o'clock

A m., and recorded in

Liber 6 of CORNERS

on page 283

Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

1/4 corner section 24 & 25, T47N, R46W

I, John R. Garske, in a field survey on November 14, 1997 hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by Austin Burt, D.S. on June 11, 1851. He set a wood post from which:
Sugar 10" S37°W 9 links
Sugar 14" N03°E 62 links
1/4 cor. set @ 40.08 chains

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I established the corner at the centerline of River Road opposite an ancient barbwire, rockwall fence running west. This fence line extends 1/2 mile west to the monumented section corner. This location also checks well with fence lines north along River Road to "40" lines. A fence line runs east approximately 33' north of this location, but may have been on the north side of an old lane.

(Research on file)

PEER GROUP APPROVED
Richard R. Decker 12/1/97
COUNCIL

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I set a 3/4" x 12" iron rod with a 3 1/4" alum. cap approximately 3" below the surface the centerline of River Road, from which:
- Reference monument - 2 1/2" alum. pipe monument with a 3 1/4" dia. alum. cap stamped : R.M. west - 23.77 feet, to corner in road centerline.

Steel sign rail	East	24.77 feet
6" Balsam -	N20°W -	67.40 feet
6" Maple	Due West	27.45 feet
6" Maple	S35°W	42.86 feet

Signed by

Surveyor's Michigan License No.

John R. Garske
28410

Date

