

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Gogebic
(County)

Located In: _____ Corner Code ##

1. Public Land Survey		<u>T 47N R 46W</u>	<u>M-5</u>
	T	H	
	<u>T 47N</u>	<u>R 46W</u>	<u>A-5</u>
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

Register's Office }
 Gogebic County } ss.

Received for record the
12TH day of MAY
 A. D. 1995 at 11:20 o'clock
A m., and recorded in
 Liber 5 of CORNERS
 on page 259.

Ramona Collins, Deputy
 Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Sec. Cor. Comm. to Sec's. 12, 13, 7 & 18

I, John P. Goss, in a field survey on May 6, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original Corner established by John Burt, U.S. Deputy Surveyor on September 7, 1847, as being a Hemlock post.

Original Bearing Trees: Hemlock 10" S71°E 26 links
 Ironwood 7" N75°W 3 links

John P. Goss found a 3/4" iron pin in concrete monument buried 2" by using MDOT Plans of U.S. #2, recorded it in Liber 1 on page 412 of Land Corners for Gogebic County; Top nut of Fire Hyd.- S 58° W- 47.92'; P.Pole- Due West- 24.01'; P.Pole- N 27° E- 40.36'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I founded the 3/4" iron pin in concrete monument and it checked with two (2) bearing objects in John P. Goss certification. I updated the corner monument and accessories as noted below to state and county specification.

Act 74 reseach on file with the county Register of Deeds Office.

PEER GROUP APPROVAL

Richard P. Drahm 5/11/95
 COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set a 2 1/2" brass cap with a 2" stem 1" below asphalt road surface. Cap is stamped. T47N, R45-46W, S12,13,7 & 18; 1995; P.S. 23509. I established the following bearing trees and reference objects.

Top Nut of Fire Hyd. S 60° E 48.02'
 Power Pole Due West 24.01'
 Power Pole N 27° E 40.36'
 Reference Monument consisting of a 2 1/4" x 30" aluminum monument with a 3/4" aluminum cap stamped to indicate corner position: S 33° W- 58.20'.



Signed by John P. Goss Date May 9, 1995
 Surveyor's Michigan License No. P.S. 23509