

SURVEY & REMONUMENTATION

OCT 0 8 1996

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
 Gogebic County } ss.

Received for record the
16th day of August
 A. D. 1996 at 11:10 o'clock
A m., and recorded in
 Liber 6 of CORNERS
 on page 26
Namona Collins Deputis
 Register of Deeds

Register of Deeds Stamp & File Number

For corners in Gogebic Located In: _____ Corner Code # _____
 (County)

- 1. Public Land Survey T 47N R 46-45W M-7
T 47N R 46-45W A-7
 T _____ R _____
 T _____ R _____
- 2. Property Controlling in Section S _____ T _____ R _____
 S _____ T _____ R _____
- 3. Miscellaneous Property in Section S _____ T _____ R _____
 S _____ T _____ R _____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Section corner common to Sections 13, 18, 24, 19, T47N, R46-45W.

I, John R. Garske, in a field survey on July 25, 19 96
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- On September 7, 1847, John Burt, U.S. Deputy Surveyor, surveyed the east town line and set a cedar post. the following bearing trees were established:
 14" Y. birch - S53°W - 7 linkd
 16" Y. birch - N42°E - 25 links
- In 1848, William Burt, D.S., established new BT's in subdividing T47N, R45W:
 10" Y. birch - N40°E - 25 links
 12" Y. birch - S46°E - 65 links
- In 1851, Austin Burt, D.S. established new BT's in subdividing T47N, R46W:
 8" Cedar - N42°W - 45 links 6" Y. birch - S75°E - 26 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I established the corner position at the centerline of Londo Road and an old trail running south. The distances of 2623.97' west, 2648.74' east and 2621.40' south to known corner positions were used to verify our location. This location also fits well with local fence lines and occupation lines.

Record research on file.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner position is marked with a railroad spike with punch mark set 0.2' below gravel road surface. The following bearing trees and reference objects were established: 2 1/2" diameter aluminum pipe with 3 1/4" diameter aluminum cap stamped: County Remonumentation, T47N, R46W, R45W, R.M., 13, 18, 24 19, 1996, RLS 28410 - S20°E - 33.23' with a steel sign rail 1.06' away. Another cap stamped the same as above except S11°W - 37.78' with a steel sign rail 1.29' away.
 10" Sugar - S24°-30'E - 69.31 feet
 6" Sugar (in clump of 3) - S33°W - 115.62 feet

PEER GROUP APPROVED
Richard P. Nealon 8/14/96
 COUNTY REPRESENTATIVE



Signed by John R. Garske Date 8-5-96
 Surveyor's Michigan License No. 28410

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983