

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
 Gogebic County } ss.

For corners in
Gogebic
 (County)

Located In: Corner Code #
 T 47N R 47W E-5
 T _____ R _____
 T _____ R _____
 T _____ R _____
 S _____ T _____ R _____
 S _____ T _____ R _____
 S _____ T _____ R _____
 S _____ T _____ R _____

Received for record the
1994 day of AUGUST
 A. D. 1994 at 1:15 o'clock
P m., and recorded in
 Liber 5 of CORNER
 on page 80.
Ramona Collins Deputy
 Register of Deeds

Register of Deeds Stamp & File Number

1. Public Land Survey
S-16
2. Property Controlling
 in Section
3. Miscellaneous
 Property in Sec.

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John R. Garske, in a field survey on May 16, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by William Ives in 1848. Set a post. Original Bearing Trees:

14" maple - N77°E - 29 links; 12" sugar - S32°W - 31 links

1978 survey by Ewart C. Muller, RLS 15408. Found a 1 1/2" iron pipe at corner position and recorded in Liber 1 of Land Corners, page 392. Accessories: 18" oak - N56°W - 28.52 feet; 14" poplar - N60°E - 13.46 feet; 14" Y. birch - S19°E - 28.38 feet; 6" poplar - S67°W - 23.40 feet.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found a 1 1/2" iron pipe which checks with Muller's witnesses in his certificate. I updated the corner monument and accessories as noted below to state and county specifications.

Act 74 research on file with County Register of Deeds Office.

PEER GROUP

Approved

Richard L. Duda 8/17/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I placed a 2 1/2" x 30" aluminum pipe with a 3 1/4" aluminum cap over found 1 1/2" iron pipe. Said aluminum cap is stamped: S-8, S-9, S-17, S-16, T47N, R47W, 1994, RLS 28410. I established the following bearing trees and reference objects:

- | | |
|--|-----------------------------|
| 18" oak - N56°W - 28.43 feet | 5" ash - N18°E - 36.87 feet |
| 6" ash - S80°E - 27.28 feet | 4" ash - S23°W - 11.28 feet |
| 6' steel sign post - S45°E - 1.00 feet | |



Signed by John R. Garske Date 6/10/94
 Surveyor's Michigan License No. 28410