

SURVEY & REMONUMENTATION
APR 07 1995
COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
 Gogebic County } ss.

Received for record the
16th day of DECEMBER
 A. D. 1994 at 10:45 o'clock
A m., and recorded in
 Liber 5 of CORNERS
 on page 172
Ramona Collins Deputy
 Register of Deeds

Register of Deeds Stamp & File Number

For corners in Gogebic (County) Located In: Corner Code #F-1

1. Public Land Survey Section 4 T 47N R 47W _____
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____
 One-quarter corner common to Section 4, T47N, R47W and
 Section 33, T48N, R47W.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		

I, John R. Garske, in a field survey on December 7, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by William Ives, Deputy Surveyor, in 1848. Original corner was a sugar post and original bearing trees are: hemlock 18" - N37°E, 12 links (7.92'); hemlock 16" - N67°W, 22 links (14.52').

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence could be found due to road construction. Re-established the corner position by single proportionate measurement. Corner set on line and midway between section corners to the east and west. The corner falls approximately one foot south of the paved road centerline and six feet west of a fence to the north which runs approximately 200 feet northerly and stops at a creek.

Record research form on file with County Register of Deeds office.

PEER GROUP

Approved

Richard P. Deahn 12/15/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set a 2 1/2" brass cap with a 2" stem 2" below asphalt road surface. Cap is stamped: County Remonumentation; T48N, R47W, 1/4; S-33, S-4; T47N, 1994; RLS 28410. I established the following bearing trees and reference objects: Power Pole #300-N78°E, 176.39 feet; Power Pole #299 - N65°W, 88.83 feet; twin 6" elm - S68°W, 92.53 feet. Reference monument consisting of a 2 1/2" x 30" aluminum pipe with a 3 1/4" aluminum cap stamped to indicate the corner position - due north, 43.68 feet with a 6' steel rail with sign 1.32 feet away.

Signed by John R. Garske Date 12/14/94
 Surveyor's Michigan License No. 28410

