

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>47N</u> R <u>47W</u>	<u>E-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register's Office }  
Gogebic County } ss.

Received for record the  
21<sup>ST</sup> day of JULY  
A. D. 1995 at 1:50 o'clock  
P m., and recorded in  
Liber 5 of CORNERS  
on page 281.  
*Ramona Collins, Deputy*  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_  
One-quarter corner common to Sections 4 and 9, T47N, R47W

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3			●									
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, John R. Garske, in a field survey on April 17, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- On August 30, 1848, William Ives set a post from which a 10" sugar bears S65°E, 10 links and a 6" sugar - N47°W, 12 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence could be found. I set the corner at the fence line intersection of ancient fence lines to the west, north and south along with a rock wall/tree line to the east across Olson Road. North-south fence line lines up with centerline of Olson Road extended. This corner position checks with measurements to the east and west and is the most probable location for the corner position.

Corner research on file with Register of Deeds.

PEER GROUP APPROVED

*Richard P. Dedmon* 7/18/95  
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I set a 3/4" diameter x 30" long rebar with a 3 1/4" diameter aluminum cap stamped: County Remonumentation; T47N, R47W; 1/4; S-4; S-9; 1995; R.L.S. 28410, from which I established the following bearing trees and/or reference objects:

- 10" oak - N22°E - 22.99 feet
- 3" maple - S38°E - 11.05 feet
- 8" oak - N39°W - 9.44 feet
- 6' steel rail with sign - S42°E - 3.52 feet.

Corner is located on top of rock bluff set in rock pile and 150 lbs. of concrete.

Signed by John R. Garske Date 5/4/95  
Surveyor's Michigan License No. 28410

