

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
 Gogebic County } ss.

Received for record the
19th day of August
 A. D. 1994 at 1:20 o'clock
P m., and recorded in
 Liber 5 of CORNERS
 on page 88
Ramona Collins, Deputy
 Register of Deeds

Register of Deeds Stamp & File Number

For corners in

Gogebic
 (County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|---------------------------|------------|
| 1. Public Land Survey
<u>S-16</u> | T <u>47N</u> R <u>47W</u> | <u>F-7</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling
in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous
Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, John R. Garske, in a field survey on May 31, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by William Ives in 1848. Corner is a 8" fir, original bearing tree: 8" spruce - S35°W - 20 links.

1976 survey by Ewart C. Muller, RLS 15408. Restored corner from Michigan Department of State Highways plan of U.S.-2, dated 1969 by J. Smallwood, R.L.S., as recorded on Liber 1 of Land Corners, page 308.

Accessories: P. Pole - S04°W - 35.30 feet; East edge catch basin - Due West - 12.08 feet; Top of hydrant - N75°W - 106.18 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found a 1" x 3" iron pipe with a 2 1/2" brass cap in poor condition, marking the corner position, which checks with Muller's witnesses in his certificate. I updated the corner monument and accessories as noted below to state and county specifications.

Act 74 research on file with County Register of Deeds Office.

PEER GROUP


Approved

Richard L. Orphan 8/17/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the found iron pipe with a 2 1/2" x 30" aluminum pipe with a 3 1/4" aluminum cap stamped: 1/4, S-16, S-21, T47N, R47W, 1994, RLS 28410. I established the following bearing trees and reference objects:

- Steel sign post - S42°E - 1.01 feet
- Power pole - S04°W - 35.30 feet
- Chiseled "X" on catch basin - Due West - 12.14 feet
- Top of hydrant - N75°W - 106.18 feet
- Yield sign post - N48°E - 10.13 feet.



Signed by John R. Garske Surveyor's Michigan License No. 28410

Date 6/10/94