

SURVEY &  
REMONUMENTATION  
FEB 18 1994  
COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County } ss.

For corners in

Gogebic  
(County)

Located In:

Corner Code =#

- |                                    |                           |            |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey              | T <u>47N</u> R <u>47W</u> | <u>G-1</u> |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |

Received for record the  
30<sup>th</sup> day of DECEMBER  
A. D. 1993 at 12:25 o'clock  
P m., and recorded in  
Liber 4 of CORNERS  
on page 329  
*Betty Lavin Deputy*  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Section corner 3 & 4, T47N, R47W, S-33 & S-34, T48N, R47W.

December 15 19 93

I, John R. Garske, in a field survey on \_\_\_\_\_, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Sugar post set by William Austin Burt, August 1848.

Elm 14" - N70°E - 25 links  
Elm 12" - N7°W - 11 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence found. Found a P.K. nail at the corner location at the center line intersection of Vanderhagen and North Star Roads. This corner position has been used and accepted as the section corner in several surveys of record, by area residents and the County Road Commission.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced nail with an 8" cotton gin spike and established the following bearing trees and/or reference objects:

Light pole - N21°E - 84.24 feet  
Telephone pole - S50°E - 47.88 feet  
Power pole - S34°W - 62.30 feet  
Power pole - N43°W - 49.94 feet

Set two reference monuments being 2 1/2 x 30" aluminum Bernsten monuments with 3 1/2" caps stamped: County Remonumentation, 1993, S-3, S-4, T47N, R47W, S-33, S-34, T48N, R47W RLS 28410. - N45°E - 60.00 feet and steel rail 2.00 feet and a reference monument - Set at S57°W - 61.00 feet and steel rail 1.99 feet.

Signed by John R. Garske Date 12/21/93

Surveyor's Michigan License No. 28410