

SURVEY & RECONSTRUCTION

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office } ss.
Gogebic County }

Received for record the
30th day of DECEMBER
A. D. 1993 at 12:25 o'clock
P. m., and recorded in
Liber 4 of CORNERS
on page 330
Betty Soar, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

For corners in

Gogebic
(County)

Located In:

Corner Code #

- 1. Public Land Survey Section 4 T 47N R 47W G-2
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

- 4. Lot No. , Recorded Plat
5. Private Claims

One-quarter corner common to Sections 3 and 4, T47N, R47W.

December 22 93

I, John R. Garske, in a field survey on 19, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by William Ives, Deputy Surveyor, in 1848. Original corner was a wooden post and original bearing trees are:

- Yellow birch 8" - N27°E - 41 links - (27.06 feet)
Yellow birch 14" - S15°W - 14 links (9.24 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a railroad spike 3" below new pavement at the one-quarter corner location. This corner position has been used by several surveyors in surveys of record over a period of 16± years. It is set at the center line intersection of Nylund and Vanderhagen Roads in accordance with 1938 notes from a U.S.D.A. survey noting a monument set which apparently was destroyed. I am accepting this corner position as the most probable location of the true one-quarter corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A found railroad spike 3" below the pavement marks the corner from which I established:

- Two reference monuments consisting of 2" x 30" aluminum monuments with 3 1/2" diameter aluminum tablets stamped to identify the R.M. and corner location as follows:
1- Reference monument - N46°W - 43.81 feet - 1.69 feet to steel sign post.
2- Reference monument - due east - 24.00 feet - 0.95 feet to steel sign post
3- Power Pole - S44°E - 36.36 feet
4- 20" sugar - S80°W - 114.66 feet

Signed by


John R. Garske

Date

12/23/93

Surveyor's Michigan License No.

28410



FORM APPROVED BY MICHIGAN BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1993