

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
 Gogebic County } ss.

For corners in

Gogebic
 (County)

Located in:

Corner Code #

- | | | |
|---------------------------------------|---------------------------|------------|
| 1. Public Land Survey
<u>S-16</u> | T <u>47N</u> R <u>47W</u> | <u>G-5</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling
in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous
Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Received for record the
19TH day of AUGUST
 A. D. 1994 at 1:15 o'clock
P m., and recorded in
 Liber 5 of CORNERS

on page 82
Ramona Collins, Deputy
 Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, John R. Garske, in a field survey on May 11, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by William Ives in 1848. Set a post. Original Bearing Trees:
 12" Y. birch - S13°E - 28 links; 10" Y. birch - N41°W - 22 links

1978 survey by John P. Goss, RLS 23509, and Ewart C. Muller, RLS 15408. Found 1 1/2" iron pipe below pavement from ties furnished by Gogebic County Road Commission and recorded in Liber 1 of Land Corners, page 394. Corner accessories: P. Pole - Due West - 34.08 feet; P. Pole - N59°E - 85.00 feet; Birch - S51°E - 63.82 feet.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found a P.K. nail at the corner position in newly paved road and checked with witnesses on Goss/Muller certificate. I updated the corner monument and accessories as noted below to state and county specifications.

Act 74 research on file with County Register of Deeds Office.

PEER GROUP Approved

Richard L. Dean 8/17/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the P.K. nail with a 2 1/2" brass cap with a 2" stem set with anchoring cement 1 1/2" below pavement, brass cap is stamped: S-9, S-10, S-15, S-16, T47N, R47W, 1994, RLS 28410. I established the following bearing trees and reference objects: Reference monument consisting of a 2 1/2" x 30" aluminum pipe with a 3 1/4" aluminum cap stamped to indicate corner position - N38°W - 45.00 feet w/steel sign post 1.92 feet away.

Power Pole - Due West - 34.08 feet
 Power Pole - N59°E - 85.00 feet
 8" birch - S51°E - 63.82 feet

Signed by John R. Garske Date 6/10/94
 Surveyor's Michigan License No. 28410

