

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
 Gogebic County } ss.

Received for record the
19~~74~~ day of AUGUST
 A. D. 1994 at 1:15 o'clock
9 m., and recorded in
 Liber 5 of CORNERS
 on page 85.
Ramona Collins Deputy
 Register of Deeds

Register of Deeds Stamp & File Number

For corners in Gogebic (County) Located In: Corner Code #

1. Public Land Survey <u>S-15</u>	T <u>47N</u> R <u>47W</u>	<u>G-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, John R. Garske, in a field survey on May 5, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by William Ives in 1848. Set a post. Original Bearing Trees:
 3" fir - S70°W - 4 links; 3" spruce - N70°E - 3 links

1978 survey by John P. Goss, RLS 23509 and Ewart C. Muller, RLS 15408. Found a railroad spike with punchmark at corner position and recorded in Liber 1 of Land Corners, page 396. They replaced the R.R. spike with a 1/2" x 18" iron rod from which a P. Pole bears S30°W - 29.90 feet and a P. Pole - S85°E - 36.35 feet.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found a P.K. nail at the corner position and checked with Goss/Muller witnesses in their certificate. I updated corner monument and accessories as noted below to state and county specifications.

Act 74 research on file with County Register of Deeds Office.

PEER GROUP **Approved**

Richard L. Ordan 8/17/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set a 2 1/2" brass cap with 2" stem set 1" below pavement surface, cap is stamped: 1/4, S-16, S-15, T47N, R47W, 1994, RLS 28410. I established the following bearing trees and reference objects: reference monument consisting of a 2 1/2" x 30" aluminum pipe with a 3 1/4" aluminum cap stamped to indicate corner position.

- RM - Due West - 30.00 feet w/steel sign post 1.09 feet away.
- Power Pole No. 3 - S81°E - 36.35 feet
- Power Pole No. 7 - S35°W - 29.90 feet
- N.W. corner of gal. steel fence post - N22°E - 101.40 feet

Signed by John R. Garske Date 6/10/94
 Surveyor's Michigan License No. 28410

