

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
 Gogebic County } ss.

Received for record the
19th day of August
 A. D. 1994 at 1:20 o'clock
P m., and recorded in
 Liber 5 of CORNERS
 on page 90
Barbara Collins, Deputy
 Register of Deeds

For corners in

Gogebic
 (County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|---------------------------|------------|
| 1. Public Land Survey <u>S-22</u> | T <u>47N</u> R <u>47W</u> | <u>G-8</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, John R. Garske, in a field survey on May 10, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by William Ives in 1848. Set a post. Original Bearing Trees:
 14" Y. birch - N22°W - 8 links; 10" Y. birch - S60°E - 9 links

Original Plat of Ironwood - 1885 and Case and Longyear's Addition - 1887. Set 1" iron stake.

1976 survey by Ewart C. Muller, RLS 15408. Found 1" iron stake as called out in above plat and recorded in Liber 1 of Land Corners, page 191. Accessories: P. Pole - S14°W - 76.56 feet; P. Pole - N51°W - 62.8 feet; P. Pole - N06°W - 59.16 feet.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found the 1" iron stake marking the corner position and checked with Muller's witnesses in his certificate. I updated the corner monument and accessories as noted below to state and county specifications. Corner is approximately 1 foot off back of sidewalk.

Act 74 research on file with County Register of Deeds Office.

PEER GROUP **Approved**

Richard L. Deahn 8/17/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I set a 2 1/2" x 30" aluminum pipe with a 3 1/4" aluminum cap stamped: 1/4, S-21, S-22, T47N, R47W, 1994, RLS 28410, over the 1 inch iron stake found. I established the following bearing trees and reference objects:

- Power Pole - N04°W - 59.36 feet
- Power Pole - S11°W - 76.29
- N.W. Cor. House No. 416 - S75°E - 19.43 feet
- S.W. Cor. Garage @ House No. 420 - N23°E - 63.81 feet

Signed by John R Garske Date 6/10/94
 Surveyor's Michigan License No. 28410

