

SURVEY & REMONUMENTATION

SEP 29 1994

Commissioner

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office } ss.
 Gogebic County }

Received for record the
16 day of SEPT
 A. D. 1994 at 4:00 o'clock
P m., and recorded in
Liber 5 of CORNERS
 on page 114
Raymond Collins, Deputy
 Register of Deeds

Register of Deeds Stamp & File Number

For corners in

Gogebic
 (County)

Located In:

Corner Code #

- | | | |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey S-15 | T <u>47N</u> R <u>47W</u> | <u>H-5</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

One-quarter corner common to Sections 10 and 15, T47N, R47W

I, John R. Garske, in a field survey on July, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5				●								
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by William Ives, D.S. in 1848. A yellow birch is the 1/4 corner. Original bearing trees: Y. birch 4" - N04°E, 3 links.

The 1/4 corner was found by Ewart Muller, RLS 15408, in July of 1979 consisting of a 1 1/2" iron pipe set in concrete. He recorded the corner in Liber 1 of land corners, P. 496. Accessories: Maple 6" - N75°W, 9.82 feet; Basswood 3" - Due South - 5.35 feet.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found the 1 1/2" iron pipe marking the corner position which checks with the witnesses on the certificate. I updated the corner as noted below to bring it up to county and state specifications.

Act 74 research on file with County Register of Deeds Office.

PEER GROUP

Approved

Richard L. Dralun

9/14/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I placed a 2 1/2" brass cap with a 2" stem set in anchoring cement on top of the found iron pipe at the corner position. Cap is stamped S-10, S-15 T47N, R47W, 1/4, 1994, RLS 28410. I established the following bearing trees and reference objects: Existing maple 7" - N75°W, 9.82 feet; Existing ash 4" - Due South - 5.35 feet; R. maple - 3" - S51°E, 12.03 feet; Ash 3" - N85°E, 14.32 feet (slope); Steel sign post - S62°W - 1.95 feet away.

Signed by John R. Garske
 Surveyor's Michigan License No. 28410

Date 8/29/94



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983