

SURVEY & REMONUMENTATION

SEP 29 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County }

Received for record the
16 day of SEPT
A. D. 1994 at 4:10 o'clock
7 m., and recorded in
Liber 5 of CORNERS
on page 127
Ramona Collins Odey
Register of Deeds

For corners in COMMISSION
Gogebic
(County)

Located In: Corner Code #
T 47N R 47W H-9
T _____ R _____
T _____ R _____
T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____

Register of Deeds Stamp & File Number

- Public Land Survey S-27
- Property Controlling in Section
- Miscellaneous Property in Sec.
- Lot No. _____, Recorded Plat _____
- Private Claims _____

One-quarter corner common to Sections 22 & 27, T47N, R47W

I, John R. Garske, in a field survey on July, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by William Ives, D.S., in 1848. Set wood post. Original bearing trees: Spruce 8" - S08°W, 15 links; Fir 5" - N04°W, 12 links.

The 1/4 corner position was found by Ewart C. Muller, RLS 15408 in June 1976 and marked by a 1/2" iron in 4" diameter by 48" long concrete monument. The corner was recorded in liber 1 of land corners P. 188. Accessories: P. pole - N75°E, 46.10 feet; P. pole - S60°E, 54.00 feet; P. pole - due south - 27.89 feet.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found a P.K. nail marking the corner position which checks with the witnesses in the certificate. The monument was destroyed during road excavation. I updated the corner as noted below to bring it up to county and state specifications.

Act 74 research on file with County Register of Deeds Office.

PEER GROUP

Approved

Richard P. Dralun

9/14/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the found P.K. nail with a 2 1/2" brass cap with a 2" stem set in anchoring cement 1 1/2" below pavement. Cap is stamped S-22, S-27, T47N, R47W, 1/4, 1994, RLS 28410. I established the following reference objects: One reference monument consisting of a 2 1/2" x 30" aluminum pipe with a 3 1/4" aluminum cap stamped to indicate the corner position as follows: R.M. - N33°E, 20.03 feet - with a steel sign post 1.16 feet away; P. pole - S65°W, 56.05 feet; P. pole - S07°W, 27.83 feet; P. pole - S61°E, 53.95 feet.

Signed by John R Garske
Surveyor's Michigan License No. 28410

Date 8/29/94

