

**SURVEY &
REMONUMENTATION**

SEP 29 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in

Gogebic
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey | T <u>47N</u> R <u>47W</u> | <u>I-3</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Received for record the
16th day of Sept.

A. D. 1994 at 3:50 o'clock
P m., and recorded in

Liber 5 of CORNERS

on page 108

Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section corner common to Sections 2, 3, 10 & 11, T47N, R47W

I, John R. Garske, in a field survey on July, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by William Ives, D.S., in 1848. Set wood post. Original bearing trees: Lynn 16" - S33°E, 36 links; Sugar 10" - N56°W, 29 links.

The corner position was found by Ewart Muller, RLS 15408 in May of 1976 consisting of a concrete plat monument 2 feet below the road surface and a P.K. nail set in the pavement which was found by using Gogebic County Road Commission witnesses. He recorded the corner in Liber 1 of land corners, P. 186. Accessories: P. pole - S47°E, 47.93 feet; P. pole - S42°W, 48.40 feet; P. pole - N40°W, 39.59 feet; P. pole - N30°E, 59.51 feet.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found a 3/4" x 2" long bolt set in the pavement marking the corner position which checks with Muller's witnesses in his certificate. I updated the corner as noted below to bring it up to county and state specifications.

Act 74 research on file with County Register of Deeds Office.

PEER GROUP

Approved

Richard P. Orphan

9/14/94



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the found bolt with a 2 1/2" brass cap with 2" stem in anchoring cement. Cap is stamped: S-2, S-3, S-10, S-11, T47N, R47W, 1994, RLS 28410. I established the following reference objects: A reference monument consisting of a 3/4" rebar 30" long with a 3" aluminum cap stamped to indicate the corner position as follows: R.M. - S46°E, 45.95 feet with a sign on a power pole 1.37 feet away; P. pole - N34°E, 59.53 feet; P. pole - N46°W, 48.45 feet; P. pole - S53°W, 48.44 feet.

Signed by John R. Garske

Date 8/31/94

Surveyor's Michigan License No. 28410