

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office } ss.
 Gogebic County }

For corners in

Gogebic
 (County)

Located In: Corner Code #

- | | | |
|---------------------------------------|---------------------------|------------|
| 1. Public Land Survey
<u>S-12</u> | T <u>47N</u> R <u>47W</u> | <u>K-4</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling
in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous
Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Received for record the
19th day of AUGUST
 A. D. 1994 at 1:15 o'clock
P m., and recorded in
 Liber 5 of CORNERS
 on page 78
Ramona Collins, Deputy
 Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, John R. Garske, in a field survey on May 5, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by William Ives in August of 1848. Set a wood post. Original Bearing Trees:
 Sugar 16" - N27°E - 21 links; Hemlock 12" - S21°W - 38 links
 1938 survey by U.S.D.A. Set a 5" square concrete monument with a stamped bronze cap.
 Bearing trees: 14" elm - S.S.W - 61.22 feet; 14" maple - S.W. - 73.48 feet; 5" poplar - N.W. - 18.46 feet.

1987 survey by John R. Garske, RLS 28410. Found and accepted 1938 monument as described above and recorded in Liber 3 of Land Corners, page 254. Accessories used below.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found a broken 5" square concrete monument set by U.S.D.A. in 1938. Bronze cap on monument is stamped to identify corner. Replaced broken monument and updated accessories as noted below to state and county specifications. 1988 accessories noted in L.C.R.C. are in good condition and used below.

Act 74 research on file with County Register of Deeds Office.

PEER GROUP

Approved


Richard L. Duda 8/17/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set a 2 1/2" x 30" aluminum pipe with a 3 1/4" aluminum cap stamped: 1/4, S-11, S-12, T47N, R47W, 1994, RLS 28410. I established the following bearing trees and reference objects:
 Power pole - N32°W - 45.12 feet
 4" ash - S07°W - 28.80 feet
 28" maple - S54°W - 73.41 feet

Set a reference monument consisting of a 2 1/2" x 30" aluminum pipe with a 3 1/4" aluminum cap stamped to indicate corner position. RM - N77°E - 32.03 feet w/steel sign post 0.96 feet high.

Signed by John R. Garske Date 6/10/94
 Surveyor's Michigan License No. 28410



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983