

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

Register's Office }  
 Gogebic County } ss.

For corners in \_\_\_\_\_

Received for record the  
19<sup>th</sup> day of AUGUST

_____	Located In:	Corner Code #:
<u>Gogebic</u>		
1. Public Land Survey	T <u>47N</u> R <u>47W</u>	<u>K-6</u>
<u>S-14</u>	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling	S _____ T _____ R _____	<u>Leg. #1</u>
in Section	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

A. D. 1994 at 1:20 o'clock  
P m., and recorded in  
 Liber 5 of CORNERS  
 on page 86  
Barrona Collins, Deputy  
 Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, John R. Garske, in a field survey on May 5, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by William Ives, D.S., in 1848.

Original Bearing Trees:

- Cedar - 3" - N42°E - 03 links
- DO - 3" - N65°W - 11 links

The corner position was found and remarked by Ewart C. Muller, RLS 15408, in July of 1977 and recorded in Liber 1 of land corners on page 326.

Accessories: P. Pole - N40°W-35.13'; P. Pole - N47°E-41.84'; P. Pole - S46°E-43.21'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found a P.K. nail marking the corner position which checks with Mullers witnesses in his certificate. I did not remonument the corner position in the centerline intersection of Jackson and Crestview Roads due to new road construction which will be taking place. I did upgrade the accessories as noted below to State and County specifications.

Act 74 research on file with County Register of Deeds Office.

**PEER GROUP**      **Approved**

Richard L. Drah      8/17/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A P.K. nail marks the corner position from which I established the following bearing objects:

I set reference monument #1 consisting of 2 1/2" diameter x 30" long aluminum pipe with a 3 1/4 inch diameter aluminium cap stamped to note the corner position as follows:

- R.M. #1 - N37°W - 48.57 feet - steel sign post - 0.90 feet
- R.M. #2 - S36°W - 43.51 feet - (3/4" diameter aluminum rod - 4 feet long with a 3 1/4" diameter stamped aluminum cap) - steel sign post - 0.93 feet
- Guy Pole #13 - 8/49 - S44°E - 43.16 feet (see sketch on back)
- Power Pole #103 - N53°E - 41.73 feet

Signed by John R Garske Date 6/10/94  
 Surveyor's Michigan License No. P.S. 28410



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983

