

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

Register's Office }  
 Gogebic County } ss.

Received for record the  
19<sup>TH</sup> day of AUGUST  
 A. D. 1994 at 1:10 o'clock  
P m., and recorded in  
 Liber 5 of CORNERS  
 on page 73  
Ramona Collins, Deputy  
 Register of Deeds

Register of Deeds Stamp & File Number

For corners in

Gogebic  
 (County)

Located In:

Corner Code #

- |                                       |                           |            |
|---------------------------------------|---------------------------|------------|
| 1. Public Land Survey<br><u>S-1</u>   | T <u>47N</u> R <u>47W</u> | <u>L-1</u> |
|                                       | T _____ R _____           | _____      |
|                                       | T _____ R _____           | _____      |
|                                       | T _____ R _____           | _____      |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____   | _____      |
|                                       | S _____ T _____ R _____   | _____      |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____   | _____      |
|                                       | S _____ T _____ R _____   | _____      |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John R. Garske, in a field survey on May 5, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

**Original survey by William Austin Burt in 1847, set Ironwood post. Original Bearing Trees:**

Sugar 5" - N41°E - 29 links  
 Hemlock 6" - N46°W - 4 links

U.S.D.A. survey in 1938. Set a 5" x 42" concrete monument with stamped bronze cap. Chiseled "X"s in bedrock as witnesses.

Survey by John R. Garske, RLS 28410, in August of 1988. Found chiseled "X"s from U.S.D.A. survey. Reestablished corner position from these witnesses. Corner position matches GLO calls. Recorded in Liber 3 of Land Corners on page 253 by J. Garske.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8" x 30" rebar with aluminum stamped cap with stone pile around it. Remonumented the corner position and updated the accessories as noted below to bring them up to state and county specifications. Corner accessories by Garske in good condition and are noted again below.

Act 74 research on file with County Register of Deeds Office.

**PEER GROUP**

**Approved**

Richard L. Dralun

8/17/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced 5/8" rebar with a 3/4" x 30" long rebar with a 3" aluminum cap stamped: County Monumentation, T48N, R47W, T47N, 1/4, S-36, S-1, 1994, RLS 28410, from which I established the following accessories: (shallow bedrock in area did not allow a standard aluminum monument)

- 4" ash - S44°E - 52.76 feet
- 4" ash - N11°W - 7.76 feet
- 3" ash - Due East - 21.74 feet
- 6" Ironwood - S55°W - 10.14 feet

Signed by

John R. Garske

Date

6/10/94

Surveyor's Michigan License No.

28410

