

**SURVEY & REMONUMENTATION**

SEP 29 1994

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County } ss.

Received for record the

16 day of SEPT  
A. D. 1994 at 4:00 o'clock  
P m., and recorded in  
Liber 9 of CORNERS  
on page 116  
Rasmona Collins, Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

For corners in

Gogebic  
(County)

Located in:

Corner Code =#

1. Public Land Survey	T <u>47N</u> R <u>47W</u>	<u>L-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

**One-quarter corner common to Sections 12 & 13.**

I, John R. Garske, in a field survey on June 22, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- On August 25, 1848, William Ives set a wood post from which a B. ash 4" bears N53°E, 22 links and a Fir 6" bears S40°W, 07 links.
- 1938 survey by U.S.D.A. Set a 5" x 42" concrete monument with stamped bronze cap 8" below road surface from which a fence post N47°E, 46.38 feet; P. pole - S45°E, 39.55 feet; fence post - S47°W, 46.46 feet.
- August 1988 survey by J.R. Garske, RLS 28410. Re-established corner from M.D.O.T. Highway plans. Set P.K. nail at corner location as per recordation certificate L. 3, Pg. 262.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found a P.K. nail marking corner position and checked with witnesses from my previous recordation certificate. I dug up road at the corner location and found a 3/4" x 8" iron pin resting atop of a broken concrete monument 12" below road surface. I updated the corner as noted below to bring it up to county and state specifications.

Act 74 research on file with County Register of Deeds Office.

**PEER GROUP**

**Approved**

Richard L. Drahn

9/14/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I reset the found 3/4" x 8" iron pin inside a 2 1/2" x 9" aluminum pipe with a brass cap on top encased in 8" x 12" of concrete, brass cap is stamped: 1/4; S-12; S-13; T47N, R47W, 1994, RLS 28410. I established the following bearing trees and reference objects: A reference monument consisting of a 2 1/2" x 30" aluminum pipe with a 3 1/4" aluminum cap stamped to indicate the corner position as follows: N46°W, 51.22 feet with steel sign post 1.42 feet away; 13" spruce S27°W, 73.51 feet; 15" R. pine N34°W, 55.10 feet; P. pole #12 - 49/05 - N46°E, 45.51 feet.

Signed by

John R. Garske

Date

8/31/94

Surveyor's Michigan License No.

28410



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983