

**SURVEY &  
REMONUMENTATION**

JUN 29 1995

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

Register's Office } ss.  
Gogebic County }

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>47N</u> R <u>47W</u>	<u>L-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Received for record the  
12<sup>TH</sup> day of APRIL  
A. D. 1995 at 1:15 o'clock  
P m., and recorded in  
liber 5 of COFFEES  
on page 235

Ramona Collins, Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

One-quarter corner common to Sections 25 & 36, T47N, R47W

I, John R. Garske, in a field survey on April 5, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- On August 24, 1848, William Ives set a post from which a 7" spruce bears N47°E, 38 links and a 12" Y. birch - S51°W, 31 links.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

I reestablished the corner position at the intersection of the centerline extension of Norrie Park Road and an ancient north-south fence line. This is the only possible location of this corner as it checks with measurements to occupation lines and sets in harmony with local residents.

Measurements to corners east and west were used to verify this corner position.

Record research on file with Register of Deeds.

**PEER GROUP APPROVED**  
Richard L. Dulan 4/6/95  
**COUNTY REPRESENTATIVE**

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

I set the corner approximately 36 feet south of the curved centerline of Norrie Park Road by placing at the corner position a 2 1/2" diameter x 30" long aluminum pipe with a 3 1/4" aluminum cap stamped: County Remonumentation; T47N, R47W; S-25; S-36; 1/4; 1995; RLS 28410, from which I established the following bearing trees and/or reference object:

- 6" sugar - N12°E, 83.63 feet
- 7" R. maple with fork - S39°E, 6.31 feet
- 5" Y. birch - S39°W, 29.70 feet
- 6 foot steel rail with sign - S02°E, 0.99 feet

Signed by John R. Garske  
Surveyor's Michigan License No. 28410

Date 4-6-95

