

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office } ss.
 Gogebic County }

For corners in

Gogebic
 (County)

Located In: Corner Code #

- | | | |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey | T 47N R 46W | A-5 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T <u>47N</u> R <u>47W</u> | <u>M-5</u> |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Received for record the
30th day of DECEMBER
 A. D. 1993 at 12:20 o'clock
? m., and recorded in
 Liber 4 of CORNERS
 on page 322

Betty Soare
 Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Section corner common to S-7 & 18, T47N, R46W
 and S-12 & 13, T47N, R47W.

December 28 93

I, John R. Garske, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Survey by William A. Burt, on September 7, 1842. Set maple post from which a 10" Y. birch bears N48°E - 3 links and a 6" fir bears S66°W - 14 links and a 12" fir - S33°E - 47 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence found due to road and utility construction. Found P.K. nail set by Gogebic County Road Commission Surveyor, J.P. Goss, RLS, which has been used and accepted in many surveys of record. This corner position was used in the 1969 MDOT survey of U.S. Highway 2 by John Smallwood, RLS, and is referenced in the State's right-of-way plans.



PEER GROUP APPROVED
Richard P. Washburn 3/1/95
 COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 20" long rebar. Established the following bearing trees and reference objects:

- 7" cherry - S23°W - 41.10 feet
- 6" R. pine - N61°W - 107.20 feet
- Reference monument - north - 37.38 feet. Set a 2 1/2" x 30" aluminum County Monument with a 3 1/2" stamped aluminum cap - steel sign post - 1.29 feet.
- Reference monument - N61°E - 59.15 feet. Set a 2 1/2" x 30" aluminum County Monument with a 3 1/2" stamped aluminum cap - steel sign post - 1.08 feet.

Signed by John R Garske Date 12/29/93
 Surveyor's Michigan License No. 28410