

**SURVEY &  
REMONUMENTATION  
COMMISSION**  
APR 07 1995

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Gogebic  
(County)

Located In:

Corner Code ##

- |                         |   |            |   |            |            |
|-------------------------|---|------------|---|------------|------------|
| 1. Public Land Survey   | T | <u>47N</u> | R | <u>47W</u> | <u>M-8</u> |
| Section 24              | T | _____      | R | _____      | _____      |
|                         | T | _____      | R | _____      | _____      |
|                         | T | _____      | R | _____      | _____      |
| 2. Property Controlling | S | _____      | T | _____      | _____      |
| in Section              | S | _____      | T | _____      | _____      |
| 3. Miscellaneous        | S | _____      | T | _____      | _____      |
| Property in Sec.        | S | _____      | T | _____      | _____      |

Register's Office }  
Gogebic County } ss.

Received for record the  
21<sup>ST</sup> day of OCTOBER  
A. D. 1994 at 11:15 o'clock  
A m., and recorded in  
Liber 5 of CORNER  
on page 153.  
Ramona Collins, Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

1/4 Cor. comm to sec's. 19- T47N,R46W &  
24- T47N,R47W

I, John P. Goss, in a field survey on September 9, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by Wm. A. Burt in 1848. Set spruce post.

Original bearing trees.

Cedar 10" S27°E 10 links  
Spruce 12" N63°W 27 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Iron pin placed by Newport mine survey never found.

Set by single proportion measurement between recorded section corners, as road construction has removed all monuments.

Act 74 research on file with County Register of Deeds Office.

**PEER GROUP**

**Approved**

Richard L. Duda 10/12/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A P.K. Nail marks the corner position from which I established the following bearing objects.

I set reference monuments #1 and #2 consisting of 2½" diameter x 30" long aluminum pipe with 3¼" diameter cap stamped to note the corner position as follows:

R.M. #1 S23°E 19.18' - steel sign post- 1.33'  
R.M. #2 S48°W 39.15' - steel sign post- 1.03'  
D.H. Nail & Tag in P.Pole N82°E 16.02'  
D.H. Nail & tag in P.Pole N89°W 183.17'

Signed by John P Goss

Date 9-16-94

Surveyor's Michigan License No. P.S. 23509

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													



N  
No Scale

