

SURVEY & REMONUMENTATION

JUN 29 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
 Gogebic County } ss.

Received for record the
12th day of APRIL
 A. D. 1995 at 1:15 o'clock
P m., and recorded in
 Liber 5 of CORNERS
 on page 236
Ramona Collins, Deputy
 Register of Deeds

Register of Deeds Stamp & File Number

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	S-36 T <u>47N</u> R <u>47W</u>	<u>M-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

One-quarter corner common to Sections 25 and 36, T47N, R47W and
 Sections 30 and 31, T47N, R46W.

I, John R. Garske, in a field survey on March 23, 1995,
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
 in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
 current manual of survey instructions of the United States Department of the Interior, Bureau of Land
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
 Court of Law; established, re-established, monumented, re-monumented, recovered, found as
 expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
 on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- On September 6, 1847, William Austin Burt set a sugar post from which a 8" tamarack bears N80°E, 22 links and a 8" spruce - N67°W, 17 links.
- U.S.D.A. Form 874-9 dated 1/3/36. Found square tree in good condition with a metal tag on east side of a 6" cedar post. Field personnel state they did not believe this to be a genuine land office corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I established the corner position at the centerline intersection of town roads and verified the corner position with measurements to corners, north, south and west.

Record research on file with Register of Deeds.

PEER GROUP APPROVED

Richard R. Decker 4/6/95
 COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I set a 3 1/4" brass cap stamped: T47N, R47W, R46W; S-25; S-30; S-36; S-31; 1995; RLS 28410, from which I established the following bearing trees and/or reference objects: 10" apple - N22°E, 85.81 feet; P. pole - S34°E, 41.66 feet; clump of 3 - 10" R. maple - N44°W, 100.95 feet; a reference monument consisting of a 2 1/2" diameter x 30" aluminum pipe with a 3 1/4" diameter aluminum cap stamped: County Remonumentation; T47N, R47W, R46W; S-25; S-36; S-30; S-31; 1995; R.M.; RLS 28410; N53°E, 61.87 feet; a 6 foot steel rail with sign 1.22 feet away.

Signed by John R. Garske Date 4-6-95
 Surveyor's Michigan License No. 28410

